



THE CITY OF MT. PLEASANT, MICHIGAN

Mt. Pleasant Parks & Recreation
320 W. Broadway • 48858-2447
(989) 779-5331 • (989) 773-6790 fax
www.mt-pleasant.org



PRE-BID ADDENDUM NO. 1

- Project Bid:** 2018 Island Park/Pickens Field Infield Repair & Reconditioning
- Bid Date:** Tuesday, January 9, 2018
- Time:** 1:30 p.m.
- Opening:** City of Mt. Pleasant – City Hall
320 W. Broadway Street
Mt. Pleasant, MI 48858
- Addendum Issued By:** City of Mt. Pleasant Parks Department
(989) 779-5331
- Date Issued:** December 20, 2017
- Intent:** Clarification regarding contractor questions, adjustments to bid specification and requirements.
1. Total amount of Dura Edge Classic Infield Mix on the three (3) Island Park fields shall be 100 tons per field for a total amount of 300 tons.
 2. Total amount of stone dust to be added at Pickens Fields shall be 150 tons per field for a total amount of 300 tons.
 3. Amount of existing contaminated material to be removed shall be no less than ¼ inch and no more than ½ inch. All material spoils shall be left onsite at a designated location.
 4. The total amount of infield conditioner added per field at Island Park shall be (four) 4 tons per field for a total of 12 tons. The infield conditioner shall be a 3:1 ratio of Turface Pro League Heritage Red to Dura Edge Pro Slide Engineered Top Dressing. This is a clarification to “match color of Dura Edge Classic Infield Mix” in bullet point 11 for special conditions related to Island Park.
 5. Bulk material may be staged at Pickens Field in designated location.
 6. Contractors are responsible for protecting the turf surrounding field and inside of field during scheduled work on fields.

Please acknowledge receipt of this Addendum on the first page of the revised Proposal Sheet.